



Linde Briefing for USEA

Update on DOE Post-Combustion
Capture project & CCUS activities

Leading.


THE LINDE GROUP

January 2013

Linde Overview & Focus on CCUS Pathways


PCC Technology & Update on DOE Project

Current CCUS Activities & Focus Areas

The Linde Group Overview



Founded	1879
Sales	~\$20 billion
Employees	~62,000
Countries	>100



Linde Engineering Technology-focused

Air Separation



Global #1

Hydrogen/Syn Gas



Global #2

Olefins



Global #2

Natural Gas



Global #3



Leveraging
Synergies

Linde Gas - Tonnage World-class operations

HyCO Tonnage Plants



>70 plants

ASU Tonnage Plants



>300 plants

CO2 Plants



>100 plants

ECOVAR Std Plants



>1,000 plants

Growth opportunities

Product portfolio serving mega trends

Growth markets



Clean energy




Healthcare



Leveraging Gases & Engineering business synergies

Linde pursuing all three CCS pathways

Technology Development & Solution Offering



Linde Overview & Focus on CCUS Pathways

PCC Technology & Update on DOE Project

Current CCUS Activities & Focus Areas

Overall Objective

- Demonstrate Linde-BASF post combustion capture technology by incorporating BASF's amine-based solvent process in a 1 MWel slipstream pilot plant and achieving at least 90% capture from a coal-derived flue gas while demonstrating significant progress toward achievement of DOE target of less than 35% increase in levelized cost of electricity (LCOE)

Specific Objectives


- Complete a techno-economic assessment of a 550 MWel power plant incorporating the Linde-BASF post-combustion CO₂ capture technology to illustrate the benefits
- Design, build and operate the 1MWel pilot plant at a coal-fired power plant host site providing the flue gas as a slipstream
- Implement parametric tests to demonstrate the achievement of target performance using data analysis
- Implement long duration tests to demonstrate solvent stability and obtain critical data for scale-up and commercial application

DE-FE0007453 Project Participants



Partner/ Organization	Lead contact(s)	Key Role(s)
DOE-NETL	Andrew P. Jones, Project Manager	-Funding & Sponsorship
Linde LLC	Krish Krishnamurthy, PI Stevan Jovanovic, Technical Lead	-Prime contract -Overall program management -Operations and testing
BASF	Iven Clausen (BASF SE) Sean Rigby (BASF Corp)	-OASE® blue technology owner -Basic design -Solvent supply and analysis
EPRI	Richard Rhudy	-Techno-economics review -Independent validation of test analysis and results
Southern Co./NCCC	Frank Morton Michael England	-NCCC Host site (Wilsonville, AL) -Infrastructure and utilities for pilot plant build and operations
Linde Engineering, Dresden	Torsten Stoffregen Harald Kober	-Basic engineering -Support for commissioning -Operations and testing
SFPC (Linde Eng)	Lazar Kogan Keith Christian	-Detailed engineering -Procurement and installation

Project schedule by budget period and task



Project progress and accomplishments by task (Budget Period 1)

Task#	Task Description	Key Objectives	Accomplishments
1	Program Management	Complete project management plan and implement to agreed cost and schedule.	<ul style="list-style-type: none"> - Project kick-off meeting held - Updated project management plan completed
2	Techno-economic evaluation	Complete techno-economic analysis on a 550 MWe coal-fired power plant incorporating Linde-BASF PCC technology.	<ul style="list-style-type: none"> - Techno-economic assessment completed and presented to DOE-NETL - Benefits of technology demonstrated
3	Pilot plant optimization and basic design	Define pilot plant design basis and the key features incorporated. Complete basic design and engineering.	<ul style="list-style-type: none"> - Design basis document completed and pilot plant features selected. - Basic design and engineering completed.
4	Pilot plant design and engineering	Complete detailed design and engineering of the pilot plant.	<ul style="list-style-type: none"> - Detailed engineering nearing completion (90% model)
5	Pilot plant cost and safety analysis	Complete preliminary environment, health and safety assessment for the pilot plant	<ul style="list-style-type: none"> - NEPA document completed with NCCC and DOE-NETL approval obtained - Preliminary EH&S topical report completed - Vendor packages developed and firm cost estimates obtained


Linde-BASF experience in large scale carbon capture

CO₂ capture in NG processing: Re-injection Project - Hammerfest

World's first industrial project to deliver CO₂ separated onshore from the well-stream back offshore for re-injection into a reservoir

- Partnership with StatoilHydro Petroleum
- Melkoya island near the town of Hammerfest, Norway
- CO₂ sequestration and re-injection integral part of the Hammerfest LNG project. **Linde performed design, EPC and commissioning**
- One dedicated well for CO₂ storage in a sandstone formation sealed by shale cap.
- Re-injection started in April 2008
- **BASF's OASE[®] purple process used in CO₂ capture**

700,000 tpa CO₂ capture and re-injection (part of world scale LNG project, Snøhvit, Norway)



Post combustion CO₂ capture: Challenges compared to CO₂ removal in NG/LNG plants

	NG/LNG	Flue gas
Pressure	50 – 100 bars	1 bara
CO ₂ partial pressure	1 – 40 bars	30 – 150 mbars
Flowrate	up to 60 mio scf/hr	up to 120 mio scf/hr
Gas composition	CH ₄ , C ₂ H ₆ , ..., CO ₂ , H ₂ S, COS, C _x H _y S, H ₂ O	N ₂ , O ₂ , H ₂ O, CO ₂ , (SO _x) NO _x
Treated gas specification	50 ppm – 2 % CO ₂ S < 4 – 10 ppm	CO ₂ removal rate (90 %) low amine emissions
Energy efficiency	not a key issue	of highest priority η ↘ 7-10% points




- ❑ large volume flows @ low pressure
- ❑ solvent stability
- ❑ emissions of solvent
- ❑ overall power plant efficiency losses

BASF OASE[®] blue Technology Development Designed for PCC Applications

BASF
The Chemical Company

THE LINDE GROUP

Equilibria **Kinetics** **Stability**



Fundamental Lab Scale R&D:
Advanced Solvents Screening,
Development, Optimization



BASF Miniplant,
Ludwigshafen, Germany:
Solvent Performance
Verification



0.45 MWe PCC Pilot,
Niederaussem, Germany:
Preliminary Process
Optimization



Niederaussem* pilot plant key results



>90% carbon capture rate achieved
>20% improvement in specific energy compared to MEA
New BASF solvent is very stable compared to MEA

Solutions for Large Scale PCC Plant (1100 Mw_{el} Power)

Design challenges


Optimizing CAPEX by reduced number of trains to handle 18,000 tpd CO₂

- 2 process trains selected
- reduced plot space

Compressor section

two lines per train

→ flexible turn down operation



Lower number of trains results in bigger size of components, e.g.

- Absorption column: diameter ca. 18 m, height ca. 75 m → on site fabrication required
- Pipes ducts and valves: diameters up to 7 meters
- Plot : ca. 100 m x 260 m

Concepts for a Large Scale PCC Plant

Key elements of plant costs


Main challenges

- Large equipment size requires new concepts
- Required plot area is very significant
- Alternative materials need to be assessed
- New equipment arrangements needed
- Field fabrication
- Large pipe and duct

Linde studies to address challenges


- Scaling to a very large single train
- Optimize equipment arrangement (flue gas blower, pre-cooler, absorption columns sump etc)
- Develop new column construction materials
- Optimize machinery options

Total plant cost distribution



- Engineering and supervision
- Equipment incl. columns (w/o blowers & compressors)
- Blowers & compressors
- Bulk Material
- Civil
- Construction


Simplified process flow diagram of the 1MWe pilot plant



Stream		S1	S2	S3
		Feed gas	CO ₂ Lean	CO ₂ Rich
Temperature	F	123.8	114.1	104.0
Pressure	psia	14.9	13.8	47.9
H ₂ O	vol%	13.30	9.49	2.31
CO ₂	vol%	12.14	1.45	97.67
CO	vol%	0.00	0.00	0.00
N ₂	vol%	69.36	82.85	0.01
O ₂	vol%	5.20	6.21	0.00
Flow rate (total)	mscf/hr	217.4	182.0	24.3
Flow rate (total)	lb/hr	16,517	13,209	2,782
CO ₂ Recovered	TPD			30.0

Utilities for 30_TPD Pilot Plant

LP Steam	lb/hr	3,600
El. Power	kW	190
Cooling Water	GPM	570
Makeup water	GPM	0.3



Techno-Economic Assessment: Linde-BASF PCC Plant Design for 550 MWe PC Power Plant



Specifications and Design Basis

identical to DOE/NETL Report 2007/1281


as per DE-FOA-0000403 requirements

- Bituminous Illinois #6 Coal Characteristics
- Site Characteristics and Ambient Conditions
- Pulverized Coal Boiler Design
- Subcritical Steam Turbine Design
- Steam Cycle Conditions
- Environmental Controls and Performance
- Balance of Plant
- Economic Assumptions and Methodology

UniSim Design Suite R390, integrated with


- Brian Research & Engineering ProMax[®] software for PCC parametric optimization
- BASF's proprietary package for rigorous solvent performance predictions

- Single train PCC design for ~ 13,000 TPD CO₂ capture
- 40-50% reduced plot area to 180m x 120 m



PCC – Power Plant

Typical Process Integration Option (LB-1)




PCC – Power Plant

Advanced Process Integration Option (LB-2)

BASF
The Chemical Company

THE LINDE GROUP




Comparative PCC Performance Results


Linde-BASF vs Reference DOE/NETL Case*




Energy demand for different PCC plants



Effect of PCC technology improvements on incremental energy requirement for power plant with CO₂ capture and compression



Total PCC Plant Cost




Significantly reduced total PCC plant Cost relative to DOE/NETL 2007 Reference Case #10 due to


1. Reduced coal combustion (CO₂ production) for 11.1% (LB-1) or 15.2% (LB-2)
2. Single train PCC design
3. Optimized PCC plant design

Power plant efficiency improvements and LCOE reductions with Linde-BASF PCC technology

Incremental improvements in power plant efficiency
from MEA based PCC to LINDE-BASF LB-2 Option



Incremental Reductions in Levelized Cost Of Electricity
from MEA based PCC to LINDE-BASF LB-2 Option



Detailed engineering timeline: Key dates


[illegible]

PSR: Process Safety review; P&ID: Process and Instrumentation Diagrams; RFQ: Request for quotes; Hazop: Hazard and operability study


Task 3: Design Selection Pilot Plant Layout



Optimized plant layout
to be investigated





3D Model of NCCC site with Linde-BASF Pilot Plant




Linde-BASF Pilot Plant

3D Model of Linde-BASF 1 MWe Pilot Plant



3D Model of Linde-BASF Pilot Plant modular design (3 level structure)



- Joint design basis development (Linde and SCS/NCCC) for the nominal 1 MWe pilot plant
- Leveraged Niederaussem pilot plant experience for early design selection decision on target solvent, pilot plant preliminary sizing, process control and analytical sampling and measurement
- Targeted 1 m absorber diameter size, leading to testing capability to 30 TPD CO₂ or 1.5 MWe equivalent – confirmed utility availability with upside margins
- Integrated modeling approach for detailed engineering – start with the existing NCCC facility model with tie-in points defined and integrated into pilot plant model to avoid conflicts in build phase
- Equipment and module packages sent to multiple vendors and vendor selection performed based on cost, capability and eagerness for involvement in project
- Concrete column sections evaluated but determined to impact project timeline significantly – currently allowing for swapping the SS bottom section of absorber with concrete section.
- Concrete column section engineering design to be completed in BP2 and cost proposal made during the continuation request for BP3.
- Current pilot plant equipment procurement and build schedule (BP2) requires BP2 timeframe extension by 3-months. Will explore improving the schedule.

Project progress: Key Project Milestones (Budget Period 1) Status

Budget Period 1 (Dec. 1, 2011 – Feb. 28, 2013)

- Submit project management plan (03/09/2012) ✓
- Conduct kick-off meeting with DOE-NETL (11/15/2011) ✓
- Complete initial techno-economic analysis on a 550 MWe power plant (05/04/2012) ✓
- Complete basic design and engineering of a 1 MWe pilot plant to be tested at NCCC (06/20/2012) ✓
- Execute host site agreement (10/31/2012) – completed 01/09/2013 ✓
- Complete initial EH&S assessment (10/31/2012) – Completed 12/14/2012 ✓
- Complete detailed pilot plant engineering and cost analysis for the 1 MWe pilot plant to be tested at NCCC (01/31/2013) Planned for completion by 01/31/2013

Status against Budget Period 1 decision point success criteria

Decision Point	Basis for Decision/Success Criteria	Status
Completion of Budget Period 1	Successful completion of all work proposed in Budget Period 1	On track
	Demonstrate a 10% reduction in capital costs with Linde-BASF CO2 capture process	30.5 to 34.7% for PCC and 16.6 to 17.3% for integrated power plant
	Demonstrate a LCOE increase of less than 65% over the baseline	62.2% and 58.8% for 2 options considered
	Submission of an Executed Host Site Agreement	Completed
	Submission of a Topical Report – Initial Techno-Economic Analysis	Completed
	Submission of a Topical Report – Initial EH&S Assessment	Submitted
	Submission of a Topical Report – Detailed Pilot Plant Engineering and Cost Analysis	By 1/31/2013
	Submission and approval of a Continuation Application in accordance with the terms and conditions of the award	Presentation to DOE-NETL on Jan 14, 2013

Acknowledgement: This presentation is based on work supported by the Department of Energy under Award Number DE-FE0007453.

Disclaimer: “This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.”

Linde Overview & Focus on CCUS Pathways

PCC Technology & Update on DOE Project

CCUS Activities & Focus Areas

Key Goal

- Develop repeatable commercial-scale projects
- Continue focus on technology advancement

Challenges

- Carbon value, lack of planning certainty
- Risk-sharing & value-sharing of emitter, capturer, user

Technology Development

- **Pre-Combustion:** Rectisol advancements, improved integration
- **Post-Combustion:** commercial-scale demo, 3rd gen technology
- **Oxy-Fuel:** Advanced HP oxy-fuel

Project Activities

- **Summit's Texas Clean Energy Project (TCEP)** – Odessa, TX
- **UK DECC Projects:** including oxy-fuel & pre-combustion
- Various **EOR-driven** opportunities in US and abroad including NG-based CCUS

Industry & Government Collaboration

- Coal Utilization Research Council (**CURC**)
- National Enhanced Oil Recovery Initiative (**NEORI**)

Commercial Areas of Focus

- “Bankable” arrangements
- Risk-sharing models



< 20% of people attempting to climb Mount Everest are successful in reaching the summit

... but some do!

How can we get CCUS projects over the finish line with today's "carbon valuation"??

Continued technology advancement, creative business models & rational risk-sharing